# Technical Bid Evaluation

| | | | | | |
|---|---|---|---|---|---|
| **Tender Number** | **No.BBMP/EE/DD/Ten/08/2016-17, Date: 03.02.2017** | | | **Est. Cost: Rs. 30.00 Lakhs** | **Indent No: 24625** |
| Tender Name | Improvements & construction of CC Drains left side of the 1st main road Dasarahalli in ward no. 15 Dasarahalli sub division | | | Job Code: 015-17-000004 | |
| General Information | Documents Uploaded by the Tenderer thr' e-procurement portal | | | P Code: 1771 | |
| Sl No | Requirements as per Eligibility Criteria **KW-1** | Tenderer -1 | Tenderer -2 | | |
| **Sl. No.** | **Name of the Agency** | **N SHIVANANDA ( )** | **P VIJAYA BABU ( NANDI ENTERPRISES.. )** | | |
| **1** | **Address** | #473, 2nd Cross, Opp. Bajaji Show Room, Defence Colony, Nagasandra Bengaluru - 560073 | #1504, 4th C main, 2nd stage, WOC Road, Bengaluru - 86 | | |
| **2** | **Class-I Contractor Registration with BBMP / KPWD or any state government Organisations Certificate** | KPWD Registration No:CBS/C1/CIVIL/118/2015 dt: 18.02.2015 valid till: 17.02.2020 | KPWD Registration No:CBS/C1/CIVIL/2931/2015 dt: 16.05.2015 valid till: 15.05.2020 | | |
| **3** | **Achieved in at least two financial years an average minimum financial turnover (not less than Estimated Cost of Rs.30.00 Lakhs)** | | | | |
| | 2015-16 (in Rs.Lakhs) | 6,342,265 | 5,067,591 | | |
| | 2014-15 (in Rs.Lakhs) | 14,242,711 | 8,358,889 | | |
| | 2013-14 (in Rs.Lakhs) | 3,285,630 | 1,446,760 | | |
| | 2012-13 (in Rs.Lakhs) | 9,322,475 | | | |
| | 2011-12 (in Rs.Lakhs) | 7,747,684 | | | |
| **4** | **At least one similar nature of work (not less than 50% Estimated value of contract) (Rs.15.00 Lakhs)** | | | | |
| | 2015-16 (in Rs.Lakhs) | | 1,880,439 | | |
| | 2014-15 (in Rs.Lakhs) | | | | |
| | 2013-14 (in Rs.Lakhs) | | | | |
| | 2012-13 (in Rs.Lakhs) | 2,090,938 | | | |
| | 2011-12 (in Rs.Lakhs) | | | | |
| | **Evaluator's Remarks** | Qualified | Qualified | | |

Executive Engineer
Dasarahalli Division.

## Comparative Statement

| Tender Number | BBMP/2016-17/OW/WORK_INDENT24625 |
|---|---|
| Tender Name | Improvements & construction of CC Drains left side of the 1st main road Dasarahalli in ward no. 15 Dasarahalli sub division |

| | | | | | | N SHIVANANDA | | P VIJAYA BABU | |
|---|---|---|---|---|---|---|---|---|---|
| SNo | Item Name | Unit | Estimate Quantity | Estimate Rate | Total Amount | Quoted Rate | Total Amount | Quoted Rate | Total Amount |
| 1 | Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.complete as per the direction of Engineer-in-charge of the work | Cum | 416 | 86.92 | 36158.72 | 80.0 | 33280 | 87.0 | 36192 |
| 2 | Plain cement concrete M-10 with OPC cement at 220kg with crushed 40mm down size graded granite metal course aggregate @0.84 CUM and fine agreegate @ 0.6 CM in Foundation mechanically mixed placed in foundation and compacted by vibration including curing for 14 days complete as per specifications. MORTH complete as per the direction of Engineer-in-charge of the work | Cum | 62.4 | 5972.04 | 372655.3 | 4800.0 | 299520 | 5250.0 | 327600 |
| 3 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications | Sqm | 1230 | 407.04 | 500659.2 | 300.0 | 369000 | 310.0 | 381300 |
| 4 | Design Mix M20 with OPC cement @ 320kgs with 20mm & down size graded granite metal course agreegate @ 0.69 CM an Fine agregated 0.46 cm with super plaster @ 3ltrs confirming to IS 9103-1999 Reaffirmed -2008 i.) Upto 5m height complete as per the direction of Engineer-in-charge of the work | Cum | 131.52 | 6965.26 | 916071 | 5500.0 | 723360 | 6000.0 | 789120 |
| 5 | TMT/MS bar Reinforcement KSRRB M2200-6 Supplying, fitting and placing TMT bar reinforcement in Sub-structure complete as per drawing and technical specifications complete as per specifications. MORTH specification No. 1600 & 2200. complete as per the direction of Engineer-in-charge of the work | Tonne | 6.58 | 58813.04 | 386989.8 | 63000.0 | 414540 | 59413.0 | 390937.5 |

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 6 | Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per the direction of Engineer-in-charge of the work | Cum | 427.2 | 1600 | 683520 | 1423.0 | 607905.6 | 1600.0 | 683520 |
| 7 | Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete complete as per the direction of Engineer-in-charge of the work | nos | 89 | 385.84 | 34339.76 | 300.0 | 26700 | 1000.0 | 89000 |
| 8 | Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 …… Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per the direction of Engineer-in-charge of the work | Cum | 416 | 80.8 | 33612.8 | 80.0 | 33280 | 77.0 | 32032 |
| | Total Summary Amount | | | 2964006.57 | | 2507585.60 | | 2729701.54 | |
| | % against Estimated Rate | | | | | -15.40 | | -7.91 | |
| | % against CSR | | | | | | | | |
| | Total Bid Amount | | | | | 2507585.60 (L1) | | 2729701.54 (L2) | |

As per Comparative Statement the Percentage Quoted by Contractor Sri.N SHIVANANDA is - 15.40 % Below S.R 2016-17 for approval

Executive Engineer
Dasarahalli Division